

# **NuScale SMR – On Track for Deployment**

Tony Irwin  
Technical Director  
SMR Nuclear Technology Pty Ltd

# NuScale

- Brief history
- Design and specifications
- Safety Features
- Fuel management
- NRC GDA progress
- First deployment
- Multipurpose applications (Diverse Energy Platform)
- Economics
- Industrial partners and supply chain

# Small Modular Reactors (SMRs)

- Reactors with a power output  $< 300$  MWe (IAEA), more usually  $< 200$  MWe
- Factory built reactor module

## Technologies:

- Light water reactors (coolant and moderator)
- Gen IV
  - High temperature gas reactors
  - Molten salt reactors
  - Fast neutron reactors

# Small Modular Reactors (SMRs)



- Provide reliable, low emissions power in remote locations or for small grid systems
- High level of passive or inherent safety
- Reactor vessel can be installed below ground
- Compact, factory built, transportable module – reduced on-site construction time
- Lower initial capital cost and modules can be added as demand increases
- One module shutdown for refuelling, remaining modules producing power
- Simpler to operate and maintain
- Load following capabilities
- Compact site

# Brief History of NuScale

- 2000 – Design based on MASLWR (Multi-Application Small Light Water Reactor) , a DOE funded project at Oregon State University
- 2007 – NuScale company formed, based in Corvallis, Oregon
- 2008 – NRC pre-application process commenced
- 2011 – Financial crisis, rescued by Fluor who became the major shareholder
- 2013 – won DOE grant award, first customer secured
- 2017 –Licensing application to NRC (first SMR to enter the full NRC licensing process)

# NuScale Power (USA) 60 MWe power modules

## Reactor Building




© NuScale Power, LLC. All Rights Reserved.

Up to twelve x 60MWe modules in 6m x 6m x 30m bays. Modules underground in a large common pool of water (assured heat sink). Pool water surface 1.8m below ground, pool water depth 21m

Reactor building 119m long x 60m wide, with 26m below ground. Source: NuScale Power

# Site Layout


720 MWe on 18 hectare site



Source: NuScale

# Pressurised Water Reactor (PWR)

Containment structure  
62m high x 43m dia




**Typical PWR:**

**Primary circuit** – 15 MPa, inlet 294°C, outlet 325°C (no boiling)

**Secondary circuit** – 6.2 MPa, inlet 224°C, turbine inlet 275°C



Figure 1.2-7: Steam Generator and Reactor Flow



**Steam outlet to turbine**  
3.5 MPa, 302°C

**Secondary Circuit**  
Main feed through 2 helical coil steam generators  
Feed water 149°C

**Primary Circuit**  
Natural circulation  
12.7 MPa  
Inlet 258°C  
Average core temperature 284°C  
Outlet 310°C

**Containment vessel**  
23.08 m high x 4.32m ID  
Under vacuum

**Reactor vessel**  
17.7m high x 2.74m ID

NOT TO SCALE

Figure 1.2-3: Schematic of a Single NuScale Power Module and Associated Secondary Equipment






Figure 1.2-8: Decay Heat Removal System



## Decay Heat Removal System (DHRS)

- Transfers core heat from either of the SGs to isolation condensers (heat exchangers) immersed in the common reactor pool
- 2 x 100% trains,
- Capable of decay heat removal for a minimum of 3 days without pumps or power


Figure 1.2-9: Emergency Core Cooling System



Reactor vent valves release primary system steam into containment – condenses on internal surface

As liquid level rises in containment, reactor recirculation valves open


Figure 6.3-2: Emergency Core Cooling System Operation



NOT TO SCALE

# Stable Long Term Cooling

*Reactor and nuclear fuel cooled indefinitely without pumps or power*



# NuScale SMR Additional Physical Barriers

## Conventional Designs

1. Fuel Pellet and Cladding
2. Reactor Vessel
3. Containment

## NuScale's Additional Barriers

4. Water in Reactor Pool
5. Stainless Steel Lined Concrete Reactor Pool
6. Biological Shield Covers Each Reactor
7. Reactor Building

NuScale 60MWe SMR Module





Figure 4.2-1: Fuel Assembly General Arrangement



### Control Rod Assembly (CRA)

24 individual rods in the guide tubes fixed to a top spider.  $B_4C$  pellets upper portion, silver-indium-cadmium (AIC) lower, all in 304 stainless steel tube.

## Fuel Assemblies


### AREVA NuFuel HTP-2








Standard 17 x 17 FA's,  
Length = 2.43m

Reduced enrichment axial  
blanket at top and bottom  
with a central fully  
enriched zone.

Gadolinia burnable  
poison

Figure 4.3-1: Loading Pattern for Reference Equilibrium Cycle



	A-01: Batch A Type 1, 4.05 wt% <sup>235</sup> U
	A-02: Batch A Type 2, 4.55 wt% <sup>235</sup> U, with Gadolinia
	B-01: Batch B Type 1, 4.05 wt% <sup>235</sup> U
	B-02: Batch B Type 2, 4.55 wt% <sup>235</sup> U, with Gadolinia
	C-01: Batch C Type 1, 4.05 wt% <sup>235</sup> U
	C-02: Batch C Type 2, 4.55 wt% <sup>235</sup> U, with Gadolinia
	C-03: Batch C Type 3, 2.60 wt% <sup>235</sup> U
A - Twice burned, B - Once burned, C - Fresh	

## Refuelling Schedule

24 months operating cycle

10 days to refuel module

Core contains 37 fuel assemblies

Refuel one third of the core (12/13 fuel assemblies)

Fresh fuel on periphery of core and shuffles burned fuel into the middle “out-in” refuelling

37 Fuel assemblies


9.23 tonnes UO<sub>2</sub>

Nominal 249.5 kg UO<sub>2</sub> /FA



# Site Layout

720 MWe on 18 hectare site



**Turbine cooling water requirements for 12 modules: 696 l/s, dry cooling would reduce requirements by 75% and decrease output by ~ 30 MW**

# Radioactive Waste

**Total solid waste = 126 m<sup>3</sup>/year** (2 shipping containers) for 12 module (720 MWe) plant

## **Sources of solid dry and wet waste:**

- HVAC and HEPA filters, used PPE, rags and wipes, tools = 104m<sup>3</sup>/year
- failed equipment = 0.2m<sup>3</sup>/year
- LRWS (Liquid radioactive Waste System) resins, filter cartridges, oily waste, charcoal = 7.3 m<sup>3</sup>/year
- CVCS (Chemical and volume Control System) and PCUS resins and filters = 14.2 m<sup>3</sup>/year

## **Gaseous Radioactive Waste- filter and decay:**

- moisture separator – guard bed – charcoal decay beds (2 trains, 4 beds/train) – discharge

## **Spent fuel**


- Average 6 FAs/module/year
- Stored in spent fuel pond for >5 years
- Transferred to dry casks on site

# NRC Licensing Process

- July 2008 – began pre-application interactions
- January 2017 – Generic Design Certification application to NRC (first ever SMR)
- Jan 2018 – NRC accepted that the NuScale SMR can operate without the need for safety related electrical equipment
- April 2018 – Phase 1 completed – preliminary SER with open items
- September 2020 – NRC issue Final Safety Evaluation Report (FSER)
- January 2021 – Design certified

# Comprehensive Testing Program

Our testing supports reactor safety code development and validation, reactor design, and technology maturation to reduce FOAK risk.



# NuScale Control Room Simulator



# NuScale Upper Module

Full scale mock up including upper section of containment vessel, reactor vessel head, major piping and valves, control rod drive mechanisms, module access platform

Assists in assessment of inspection and maintenance activities



# Project WIN

- Western Initiative for Nuclear (WIN) is a multi-western state collaboration to deploy a series of NuScale Power Projects
- Involved Program WIN participants: NuScale, UAMPS, Energy Northwest, ID, UT, OR, WA, WY, AZ,



***Utah Associated Municipal Power Systems (UAMPS) Carbon Free Power Project (CFPP) will be the first deployment***

# NuScale first customer

- Utah Associated Municipal Power Systems (UAMPS) – a consortium of 45 Western community-owned utilities
- Low emissions replacement for coal plants
- Site – 35 acre (14 hectare) on US Department of Energy Idaho National Laboratory (INL) site west of Idaho Falls
- Combined construction and operating licence application (COLA) by UAMPS in 2019
- Plant will be operated by Energy Northwest



# 12 Module (720 MWeG) Plant on INL Site



# Joint Use Modular Power Program (JUMP)

- Agreement with DOE for first module to be used for R&D, including integration with other energy sources
- Provision for integrating equipment with the steam producing side of the reactor, for example steam to drive an industrial process
- Could also connect with the microgrid test bed at INL
- Module will have additional instrumentation
- Agreement with DOE for second module to supply INL's energy needs under a Power Purchase Agreement

# UAMPS timescale

- 2019/20 Combined construction and operating licence application (COLA) by UAMPS
- 2021 – site preparation starts
- 2023 – start of nuclear construction
- 2026 – First 50 MW module operating
- 2027 – all 12 modules operating

*DOE awarded \$16.5m in matching funds to perform site selection, secure site and water, and prepare COLA to NRC*

# Tennessee Valley Authority (TVA)

- May 2016 – TVA submitted an Early Site Permit (ESP) Application for use of a site at Clinch River for two or more SMRs. NuScale SMR used as a technical basis for evaluation of Emergency Planning Zones (EPZ)
- August 2018 – NRC agreed that the EPZ around SMRs can be scaled down to reflect their reduced risk. For NuScale this would be reduced to the site boundary.
- June 2019 – NRC published final safety evaluation report (FSER), concluded that there are no safety concerns preventing issue of an ESP



# Small Modular Reactors

- Multipurpose
  - electricity
  - heating for buildings
  - process heat for industry
  - desalination

# NuScale Diverse Energy Platform

**Oil Refineries Study - Reduction of Carbon Emissions**  
*(Fluor and NuScale)*

**10-Module Plant** coupled to a 250,000 barrels/d refinery

**Integration with Wind Study - Horse Butte Site**  
*(UAMPS, ENW and NuScale)*

**1-Module** dedicated to UAMPS 57.6 MW wind farm



**Reliable Power for Mission Critical Facilities** *(NuScale)*

**12-Module Plant** coupled to a 100 MWe Mission Critical Facility

**Hydrogen Production Study – High-Temperature Steam Electrolysis**  
*(INL and NuScale)*

**6-Module Plant** for Emission Free Hydrogen Production

**Desalination Study – Sized for the Carlsbad CA Site**  
*(Aquatech and NuScale)*

**8-Module Plant** can produce 50 Mgal/d (190K m<sup>3</sup>/d) of clean water plus 350 MWe



# NuScale Load Following Capability

- Module output can be varied by 40%/hour. 12 module plant has 12 degrees of freedom
- Shutdown of one module of 12 module plant reduces output by 8%. A module can be returned to service in a few hours from a hot shutdown
- Each module has a 100% turbine bypass enabling fast load changes
- Can continue operating if disconnected from the grid

# Overall EPC Overnight Plant Costs


(\$1,000,000)

ITEM	2014 Dollars
Power Modules (FOAK Cost plus Fee, Transportation, & Site Assembly)	\$ 848
Home Office Engineering and Support	\$ 144
Site Infrastructure	\$ 60
Nuclear Island (RXB, RWB, MCR)	\$ 538
Turbine Island (2 buildings with 6 turbines each)	\$ 350
Balance of Plant (annex, cooling towers, etc)	\$ 225
Distributables (Temp. Bldgs., Field Staff, Const. Equip., etc.)	\$ 545
Other Costs	\$ 185
<b>Total Overnight Price</b>	<b>\$ 2,895</b>

**600 MWe**  
**12 module plant**  
**Overnight cost**  
**FOAK \$3 billion**  
**NOAK \$2.6 billion**

\$ 5,078 per kWe net

## Levelized Cost in 2015 US Dollars



FOAK with Regulated Utility Financing (IOU)

- 55% debt at 5.5%, 45% equity at 10%

\$ 106 USD



FOAK with Municipal Financing

- 100% debt at 3.5%, no equity

\$ 72 USD

**60 MWeG module \$4,200 per kWe net**

**Target LCOE \$65/MWh**



# Industrial Partnerships and Supply Chain

- **Sargent & Lundy** – development of the standard plant, additional architect engineering support
- **Doosan Heavy Industries & Construction** – co-operation and investment
- **BWXT** – optimize the engineering design for manufacturing, assembly and transportation
- **Rock Creek Innovations** – highly integrated protection system for module protection
- **Ultra Electronics Energy** – safety display and indication
- **Areva** – fuel assemblies
- **Rolls-Royce** – advanced nuclear technology
- **Curtiss-Wright** – control rod drive mechanism design
- **Sheffield Forgemasters** – RPV head
- **Concurrent Technologies Corporation** – advanced manufacturing processes for helicoil steam generators

# International

- **Canada** – Service agreement with CNSC for vendor design review in 2019. MOU's with Ontario Power Generation and Bruce Power
- **Romania** – agreement with Societata Nationala Nuclearelectrica SA
- **UK** – office established in UK, looking to deployment in the UK in the next decade
- **Jordan** – possible deployment for desalination
- **Estonia** – included in short list for feasibility study
- **Australia** – SMR Nuclear Technology Pty Ltd since 2011

- **NuScale is on track for deployment in the 2020's**